

# TRENANT

Trenant  
Dockings Cottage  
19 Trenant Vale  
Wadebridge  
Cornwall  
PL27 6AL

01208 812940  
07720 542006


## Quotation for Re-Render side wall of house

james@trenantbuilt.com

Vat Reg. No. 939 5430 94

03 Jun 2018

Quotation prepared for:



### Pricing

Total price for the entire job is as follows

Cost for agreed work: **£1638.93**

VAT (20.00%) payable: **£327.79**

Total cost including VAT: **£1966.72**

## Summary

The job is broken down into identifiable blocks of work which are each priced individually.

Description	Price Range	Price
Rendering		<b>£1215.22</b>
Fit new slate sill to underside of kitchen window		<b>£251.70</b>
Scaffold		<b>£39.24</b>
Waste		<b>£132.78</b>
<b>Total</b>		<b>£1638.93</b>

## Detailed Breakdown

Each of the blocks is broken down here in more detail to show how each price is calculated.

### 1 Rendering

To Remove existing render from front corner of house to where kitchen extension starts from above the plinth to underside of cladding.  
To render wall with two coat waterproof render with smooth sponge finish to match existing new render.

1.1	BUILDING SAND BULK BAG (1)	<b>£45.84</b>
1.2	BLUE CIRCLE MASTERCREEPE CEMENT IN PLASTIC BAGS 25KG 32.5R (12)	<b>+£100.34</b>
1.3	EXPAMET PLASTIC ANGLE BEAD PAB0152500MM (7)	<b>+£77.28</b>
1.4	EXPAMET WHITE PLASTIC BELL CAST BEAD (3 METERS) (1)	<b>+£8.48</b>
1.5	SIKA MAXMIX PLASTICISER 1 LITRE (1)	<b>+£11.33</b>
1.6	EVOPLAST WATERPROOFER 5L (1)	<b>+£15.50</b>
1.7	BREAKER (2)	<b>+£82.84</b>
1.8	LABOUR (40)	<b>+£873.60</b>

Rendering (Total): **£1215.22**

...

### 2 Fit new slate sill to underside of kitchen window

To cut and fit 25mm slate sill to underside of kitchen window and make good render around new position.  
To refit round white plastic downpipe to existing drain point

2.1	SLATE SILLS (1)	<b>£62.15</b>
2.2	OSMA DOWNPIPE WHITE 68MM (1)	<b>+£8.98</b>
2.3	OSMA DOWNPIPE CLIP (3)	<b>+£2.34</b>
2.4	OSMA WHITE DOWNPIPE JOINS (1)	<b>+£3.50</b>
2.5	LABOUR (8)	<b>+£174.72</b>

Fit new slate sill to underside of kitchen window (Total): **+£251.70**

...

### 3 Scaffold

3.1	2" TRESSELS AND PLANKS (3)	<b>£39.24</b>
-----	----------------------------	---------------

Scaffold (Total): **+£39.24**

...

### 4 Waste

To remove all waste

4.1	VISQUEEN HEAVY DUTY RUBBLE SACK RL OF 10 SACKS 558X813MM (25)	<b>£132.78</b>
-----	---	----------------

Waste (Total): **+£132.78**

...